Lakeshore Generating Station: Isolated Phase Bus

Sample document for a software demo. Fictional project.

A. Scope

Furnish isolated phase bus between the generator and the step-up transformer at a fictional power station.

B. Ratings

The bus shall be rated 15.5 kV maximum with a BIL of 110 kV. Continuous current shall be 12,000 A, self-cooled. The momentary rating shall be 350 kA peak. System frequency is 60 Hz.

C. Construction

Conductors shall be aluminum, and the enclosure shall be aluminum. The bus runs outdoor. Seal-off bushings are required at the building wall. Expansion joints shall be provided. Dry air pressurization is preferred. The assembly shall comply with IEEE C37.23.

D. Delivery

Delivery shall be within 44 weeks.