Prairie Compute Campus: Non-Segregated Phase Bus

Sample document for a software demo. Fictional project.

1. Scope

Furnish non-segregated phase bus between the 13.8 kV main transformer and switchgear at a fictional campus.

2. Ratings

The bus shall be rated 15 kV maximum with a BIL of 95 kV. Continuous current shall be 6000 A. Short-circuit rating shall be 63 kA. System frequency is 60 Hz.

3. Construction

Conductors shall be tin-plated copper. The enclosure shall be NEMA 3R and made of aluminum. Space heaters shall be provided. Flexible connections shall be provided at each termination. The assembly shall comply with IEEE C37.23.

4. Delivery

Delivery shall be within 30 weeks.