Northgate Colo: 480 V Switchboard Replacement

Sample document for a software demo. Fictional project.

A. Summary

Replace the 480 V service gear at a fictional colocation site.

B. Ratings

The gear must carry 3.2 kA on the main bus. Fault rating must be 65,000 A. Voltage is 480 V. The site is 60 Hz. The room can reach 104 F. Elevation is 2,000 ft.

C. Build

Use air circuit breakers. Provide drawout breakers. Listing to UL 1558 is required. Zone selective interlocking should be included if available. The enclosure must be NEMA 1. Top cable entry is required.

D. Schedule

Delivery must happen within 6 months of order.