# High Desert Compute Campus: 34.5 kV Outdoor Switchgear

*Sample document for a software demo. Fictional project.*

## *1. Overview*

The 34.5 kV collector switchgear is outdoors at a fictional high-altitude site.

## *2. Ratings*

Rated maximum voltage shall be 38 kV with a BIL of 150 kV. Main bus shall be 3000 A and short-circuit rating shall be 40 kA. Control power shall be 125 VDC at 60 Hz.

## *3. Construction*

The enclosure shall be NEMA 3R. The lineup shall be arc-resistant, accessibility Type 2B. Remote racking shall be provided.

## *4. Site*

The site is at 6,500 ft elevation. Equipment shall be rated for 113 F ambient. Delivery shall be within 64 weeks.