Mill Creek Data Center: Utility Service Section

Sample document for a software demo. Fictional project.

1. Scope

Furnish the utility service section for the incoming 13.8 kV feed at a fictional data center.

2. Ratings

The section shall be rated 15 kV maximum with a BIL of 95 kV. Continuous current shall be 1200 A. Short-circuit rating shall be 25 kA. System frequency is 60 Hz.

3. Construction

The enclosure shall be NEMA 3R, and the location is outdoor. Provide revenue metering and a utility disconnect. The assembly shall comply with IEEE C37.20.3.

4. Delivery

Delivery shall be within 26 weeks.