Ridgeline Data Center: Section 26 25 00, Cable Bus

Sample document for a software demo. Fictional project.

1. Scope

This section covers the 13.8 kV cable bus from the outdoor transformer yard to the main switchgear at a fictional data center.

2. Ratings

The cable bus shall be rated 15 kV maximum with a BIL of 95 kV. Continuous current shall be 3000 A. Short-circuit rating shall be 50 kA symmetrical with a momentary rating of 130 kA peak. System frequency is 60 Hz.

3. Construction

Conductors shall be copper with EPR insulation. The enclosure shall be aluminum with a ventilated enclosure design. The installation location is outdoor, and the enclosure shall be NEMA 3R. The assembly shall comply with IEEE C37.23.

4. Delivery

Delivery shall be within 28 weeks.