Summit Campus: Main Power Transformer

Sample document for a software demo. Fictional project.

A. Scope

Furnish one main power transformer for a fictional data center campus.

B. Ratings

The transformer shall be rated 30 MVA. Primary voltage shall be 34.5 kV with a BIL of 150 kV. Secondary voltage shall be 13.8 kV. Impedance shall be 8%. System frequency is 60 Hz.

C. Construction

Cooling shall be ONAN. The insulating fluid shall be natural ester. The location is outdoor. The unit shall comply with IEEE C57.12.00.

D. Delivery

Delivery shall be within 80 weeks.